

构件汇总信息明细表(包含措施筋)

工程名称: 南苑项目4#楼(导出)

编制日期: 2020-09-05

单位: kg

汇总信息	汇总信息钢筋总重kg	构件名称	构件数量	HPB300	HRB335	HRB400
楼层名称: 第2~20层 (绘图输入)				14778.371	11749.068	249429.359
暗柱/端柱	56497.317	GBZ3[694]	38			2518.26
		GBZ1[630]	437			9956.608
		GBZ2[657]	19		166.288	2698.19
		GBZ4[1158]	19		847.628	4455.386
		GBZ4a[665]	19		178.448	1188.754
		GBZ5[655]	76		1811.84	3170.34
		GBZ6[666]	19		446.88	756.333
		GBZ6[700]	19		476.672	774.459
		GBZ7[627]	57		1574.112	2733.378
		GBZ7[629]	57		1574.112	2932.821
		GBZ8[661]	19		549.024	911.126
		GBZ9[648]	19		597.056	1089.745
		GBZ7-1[632]	19		500.992	983.801
		GBZ7-1[641]	19		500.992	911.126
		GBZ5-3[676]	19		428.64	783.522
		GBZ5-2[625]	57		1214.784	2365.785
		GBZ5-1[639]	38		881.6	1650.948
		图一暗柱200[3037]	133			4867.667
		合计			11749.068	44748.249
板洞加筋	1035.994	670*600[19962]	19			337.516
		670*600[19963]	19			351.538
		670*600[19964]	19			346.94
		合计				1035.994
板负筋	8992.187	FJ-C8@130	19			410.248
		FJ-C8@150	19			772.027
		FJ-C8@180	19			331.74
		FJ-C10@180	19			992.579
		无标注FJ-C8@200	19			6485.593
		合计				8992.187
		阳台[4027]	19			1894.813

构件汇总信息明细表(包含措施筋)

工程名称：南苑项目4#楼(导出)

编制日期：2020-09-05

单位：kg

板受力筋	57257.925	其他120[4043]	19		4726.003
		其他110[4064]	19		4677.648
		其他120[4060]	19		3771.443
		厨房[4014]	19		3543.329
		卫生间前室[4012]	19		331.968
		卫生间[4008]	19		4319.441
		空调板[13651]	19		261.003
		飘窗板上[13659]	19		272.004
		飘窗板下[13682]	19		269.097
		空调板[14156]	19		32.661
		加强楼板[4030]	19		7022.837
		其他100[4058]	19		20857.953
		阳台[4023]	19		285.38
		阳台[4025]	19		271.111
		阳台[4024]	19		156.104
		其他100[4039]	19		398.411
		阳台[4026]	19		271.111
		其他100[4041]	19		263.606
		其他100[4047]	19		594.282
		其他100[4048]	19		182.856
		其他100[4051]	19		308.37
		其他100[4055]	19		130.948
		其他100[4062]	19		317.813
		其他100[4053]	19		217.265
		其他100[4045]	19		145.331
		后浇板[4048]	19		289.788
		加强楼板[4035]	19		1445.349
		合计			57257.925
构造柱	1571.756	GZ-1[14460]	38	118.104	431.832
		GZ1[14454]	76	198.588	823.232
		合计		316.692	1255.064
		GL-1[16883]	38	77.216	251.408

构件汇总信息明细表(包含措施筋)

工程名称：南苑项目4#楼(导出)

编制日期：2020-09-05

单位：kg

过梁	2488.164	1000[16864]	19		39.026
		1000[16865]	38		86.298
		1000[16866]	38		92.492
		1000[16867]	95		214.605
		1000[16868]	57		142.272
		1000[16869]	19		44.954
		1000[16873]	19		49.4
		1000[16874]	19		45.847
		1000[16875]	19		46.341
		1000[16876]	19		61.731
		1000[16882]	19		48.374
		1000-1500[16857]	19	24.32	54.682
		1000-1500[16858]	57	72.96	150.366
		1000-1500[16859]	38	54.72	99.864
		1000-1500[16861]	19	24.32	46.892
		1500-2000[16855]	19	28.272	93.328
		1500-2000[16856]	19	23.56	89.908
		窗台压顶[30137]	57	19.38	38.646
		窗台压顶[30138]	19	8.075	20.52
		窗台压顶[30139]	57	43.605	102.03
		窗台压顶[30140]	57	19.38	47.424
		窗台压顶[30141]	19	14.535	36.936
		窗台压顶[30142]	19	11.305	32.338
		窗台压顶[30143]	19	11.305	29.906
		窗台压顶[30144]	19	11.305	26.98
		窗台压顶[30146]	38	16.15	35.188
		合计		460.408	2027.756
		Q1[4790]	76		734.464
		Q1[4792]	19		596.372
		Q1[4796]	95		3290.8
		Q1[4798]	19		1066.356
		Q1[4808]	19		799.672

构件汇总信息明细表(包含措施筋)

工程名称: 南苑项目4#楼(导出)

编制日期: 2020-09-05

单位: kg

剪力墙	23588.386	Q1[4809]	38		2180.136
		Q1[4811]	19		1398.096
		Q1[4817]	19		1726.34
		Q1外[4785]	19		797.164
		Q1外[4786]	76		1064
		Q1外[4793]	114		6398.136
		Q1外[4812]	19		696.54
		Q1外[4813]	19		1314.306
		Q1外[4815]	19		1526.004
		合计			23588.386
连梁	6001.663	LL-4[692]	19	14.877	1350.862
		LL-3[681]	19	18.183	1118.283
		LL-2[662]	19	18.183	1025.487
		LL-1[663]	19	18.183	1276.287
		LL-1[673]	19	16.53	1144.788
		合计		85.956	5915.707
		KL29(3)[3015]	19	95.874	4707.421
		KL1(1)[2961]	19	46.284	3752.538
		L13(1)[2962]	19		527.63
		KL25(1)[2963]	19	26.448	2145.518
		L2(1)[2964]	38		422.788
		L2(1)[2976]	19		198.835
		L1(1)[2965]	19	14.06	734.217
		L14(1)[2966]	19		236.607
		KL2(1)[2967]	19	19.836	1567.386
		KL18(1)[2968]	19		871.188
		XL1[2969]	38	26.448	750.652
		XL3[2970]	19	29.754	608.855
		L9(1)[2971]	19	36.366	885.932
		L9(1)[2992]	19	36.366	925.433
		L9(1)[3022]	19	26.448	649.154
		KL6(1)[2972]	19	24.795	2805.084

构件汇总信息明细表(包含措施筋)

工程名称：南苑项目4#楼(导出)

编制日期：2020-09-05

单位：kg

KL22(1) [2973]	19	49.59		1725.048
KL4(1) [2974]	19	33.06		1562.959
L11(1) [2975]	19	12.654		520.258
KL17(1) [2977]	19			924.578
XL4[2978]	19	26.448		623.409
KL24(1) [2980]	19	28.101		2438.384
KL9(2) [2981]	19	31.407		1946.17
L5(1) [2982]	19	18.183		633.821
L12(1) [2983]	19			184.034
XL7[2984]	19	11.571		787.056
KL10(1) [2985]	19	26.448		2837.099
L10(1) [2986]	19	14.06		573.762
L4(1) [2987]	19			228.513
KL21(1) [2988]	19			646.513
KL19(1) [2989]	19			1329.278
XL6[2990]	19	29.754		671.536
XL6[2991]	19	26.448		637.089
KL20(1) [2993]	19	19.836		924.92
KL16(1) [2994]	19	59.508		3916.014
KL13(1) [2996]	19	16.53		1405.601
KL15(1) [2997]	19			1768.672
L15(1) [2998]	19	14.06		636.12
L16(1) [2999]	19	11.248		412.813
KL12(1) [3001]	19	13.224		865.526
KL11(1) [3002]	19	26.448		2301.261
KL33(1) [3003]	19	59.508		4245.132
L6(2) [3004]	19	59.508		1893.198
KL32(2) [3005]	19	36.366		1783.473
KL31(1) [3006]	19	13.224		1122.482
TL1[3007]	19	33.06		884.146
XL2[3008]	38	46.284		973.826
KL3(1A) [3009]	19	46.284		2377.565

梁

92969.565

构件汇总信息明细表(包含措施筋)

工程名称: 南苑项目4#楼(导出)

编制日期: 2020-09-05

单位: kg

		L19(1) [3010]	19	26.448		706.61
		KL26(2) [3011]	19	34.713		2090.703
		KL23(1) [3012]	19			906.509
		KL7(1) [3013]	19	46.284		2267.061
		KL5(1) [3014]	19	11.571		856.577
		L17(3) [3016]	19	34.713		943.35
		KL8(1) [3017]	38	33.06		2615.806
		L3(1) [3018]	19			237.006
		KL28(2) [3020]	19	49.59		1833.557
		KL30(1) [3023]	19	42.978		1978.641
		L7(1) [3024]	19	14.06		734.217
		KL14(1) [3025]	19	11.571		1134.243
		L18(1) [3026]	19	6.27		263.815
		KL27(2) [2995]	19	95.874		7041.172
		L8(1A) [3030]	19	59.508		1199.565
		XL5[3031]	19	13.224		293.987
		梁局部加宽(箍筋: C6-150) [36627]	19			82.726
		梁局部加宽(箍筋: C6-150) [36632]	38			132.924
		梁局部加宽(箍筋: C6-200) [36626]	57			196.422
		梁局部加宽(箍筋: C6-200) [36630]	19			209.665
		梁局部加宽(箍筋: C6-200) [36631]	19			50.16
		合计		1625.355		91344.21
楼梯	4459.547	AT3-1200[43788]	19			2146.05
		AT3-1250[43787]	19			2313.497
		合计				4459.547
		管井隔墙200[15144]	57	156.636		
		管井隔墙200[15145]	19	105.564		
		管井隔墙200[15175]	19	61.788		
		管井隔墙200[15176]	19	249.28		

构件汇总信息明细表(包含措施筋)

工程名称: 南苑项目4#楼(导出)

编制日期: 2020-09-05

单位: kg

管井隔墙200[15177]	19	181.336		
管井隔墙200[15178]	19	198.93		
管井隔墙200[15179]	19	73.112		
管井隔墙100[15173]	19	123.348		
管井隔墙100[15174]	19	52.212		
空调位背墙[15222]	19	62.51		
空调位背墙[15227]	19	83.752		
楼梯间隔墙-100[15232]	19	266.76		
楼梯间隔墙[15233]	19	122.208		
楼梯间隔墙[15234]	19	151.696		
外墙-楼梯间[15235]	19	334.704		
外墙-300[15143]	19	45.98		
外墙-300[15204]	133	200.83		
外墙-100[15141]	19	51.49		
外墙-100[15142]	19	49.248		
外墙[15206]	76	154.28		
外墙[15207]	19	44.46		
外墙[15208]	19	95.95		
外墙[15209]	19	135.128		
外墙[15210]	19	93.86		
外墙[15211]	19	213.18		
外墙[15212]	19	22.382		
外墙[15215]	19	33.63		
外墙[15216]	19	51.49		
外墙[15217]	19	39.52		
外墙[15218]	38	635.056		
外墙[15226]	19	144.932		
外墙[15229]	19	83.22		
外墙[15231]	19	59.47		
外墙[15240]	19	178.41		
外墙[15241]	19	75.24		
外墙[15242]	19	144.932		

构件汇总信息明细表(包含措施筋)

工程名称: 南苑项目4#楼(导出)

编制日期: 2020-09-05

单位: kg

厨房、卫生间墙-100[15185]	19	110.618		
厨房、卫生间墙-100[15186]	19	76.722		
厨房、卫生间墙-100[15187]	19	73.72		
厨房、卫生间墙-100[15188]	19	69.426		
厨房、卫生间墙-100[15189]	19	137.37		
厨房、卫生间墙-100[15190]	38	250.04		
厨房、卫生间墙-100[15191]	38	119.624		
厨房、卫生间墙-100[15192]	19	122.55		
厨房、卫生间墙-100[15193]	19	117.61		
厨房、卫生间墙-100[15194]	19	65.322		
厨房、卫生间墙-100[15195]	19	100.32		
厨房、卫生间墙-100[15196]	19	136.61		
厨房、卫生间墙-100[15197]	19	105.26		
厨房、卫生间墙-100[15198]	19	74.366		
厨房、卫生间墙-100[15201]	19	127.49		
厨房、卫生间墙-100[15202]	19	61.408		
厨房、卫生间墙-100[15203]	19	142.31		
内隔墙-100[15147]	19	112.708		
内隔墙-100[15148]	38	151.848		
内隔墙-100[15149]	19	153.216		

砌体通长拉结筋

10755.254

构件汇总信息明细表(包含措施筋)

工程名称: 南苑项目4#楼(导出)

编制日期: 2020-09-05

单位: kg

内隔墙-100[15150]	38	204.364		
内隔墙-100[15151]	19	183.312		
内隔墙-100[15152]	19	33.44		
内隔墙-100[15156]	19	111.492		
内隔墙-100[15157]	19	51.908		
内隔墙-100[15158]	19	40.736		
内隔墙-100[15159]	19	46.512		
内隔墙-100[15165]	19	16.644		
内隔墙-100[15166]	19	49.476		
内隔墙[15153]	38	342.912		
内隔墙[15154]	19	138.852		
内隔墙[15155]	19	141.816		
内隔墙[15160]	19	174.42		
内隔墙[15161]	19	24.358		
内隔墙[15162]	19	162.07		
内隔墙[15163]	19	96.672		
内隔墙[15164]	19	130.53		
内隔墙[15170]	19	55.404		
内隔墙[15171]	19	87.476		
住宅分户墙[15180]	19	230.888		
住宅分户墙[15181]	19	332.652		
住宅分户墙[15182]	19	108.68		
住宅分户墙[15183]	19	348.574		
住宅分户墙[15184]	19	232.18		
飘窗侧板[59927]	133	260.68		
飘窗侧板[59948]	19	30.856		
飘窗侧板[59963]	19	33.288		
合计		10755.254		
空调位反边2a/2b[13652]	19			131.594
空调位反边2a/2b[13661]	19			214.871

构件汇总信息明细表(包含措施筋)

工程名称: 南苑项目4#楼(导出)

编制日期: 2020-09-05

单位: kg

圈梁	7153.994	空调位反边2a/2b[13662]	38		119.51
		空调位反边2a/2b[13667]	76		238.336
		空调位反边2a/2b[13671]	19		143.431
		空调位反边2a/2b[13680]	19		191.577
		空调位反边2a/2b[13681]	19		70.775
		空调位反边2a/2b[13690]	19		154.622
		空调位反边2c[14157]	19		63.897
		阳台1a、1b[13647]	19		56.088
		阳台1a、1b[13665]	38		55.29
		阳台1a、1b[13666]	38		377.644
		阳台1a、1b[13670]	57		199.671
		阳台1a、1b[13674]	19		198.303
		阳台1a、1b[13676]	38		112.176
		阳台1a、1b[13683]	38		263.872
		阳台1a、1b[14155]	19		74.062
		飘窗反边3a[13649]	19		630.211
		飘窗反边3a[13684]	19		546.193
		飘窗反边3b[13648]	57		2145.423
		水平系梁[17983]	19	45.6	228.38
		水平系梁[17984]	19	5.7	28.12
		水平系梁[17985]	19	8.55	51.604
		水平系梁[17986]	19	19.95	107.844
		水平系梁[17987]	19	11.4	53.884
		圈梁[17981]	19	86.868	247.38
		圈梁[17982]	19	57.912	213.256
		合计		235.98	6918.014
		卫生间[11000]	19	18.05	
		卫生间[11001]	19	18.05	

构件汇总信息明细表(包含措施筋)

工程名称：南苑项目4#楼(导出)

编制日期：2020-09-05

单位：kg

卫生间[11002]	19	21.66		
卫生间[11007]	19	18.05		
卫生间[11008]	19	18.05		
卫生间[11009]	19	21.66		
卫生间前室[11006]	19	10.83		
厨房[11003]	19	32.49		
厨房[11004]	19	28.88		
厨房[11005]	19	28.88		
加强楼板[10988]	19	41.382		
加强楼板[10989]	19	18.81		
加强楼板[10990]	19	11.286		
加强楼板[10991]	19	26.334		
加强楼板[10992]	19	18.81		
加强楼板[10993]	19	26.334		
加强楼板[10994]	19	18.81		
其他100[10967]	19	10.83		
其他100[10969]	19	32.49		
其他100[10970]	19	32.49		
其他100[10971]	19	43.32		
其他100[10972]	19	10.83		
其他100[10973]	19	54.15		
其他100[10974]	19	18.05		
其他100[10975]	19	43.32		
其他100[10976]	19	10.83		
其他100[10977]	19	46.93		
其他100[10978]	19	46.93		
其他100[10980]	19	18.05		
其他100[10981]	19	50.54		
其他100[10982]	19	10.83		
其他100[10984]	19	10.83		
其他100[10985]	19	54.15		
其他100[10986]	19	25.27		

现浇板

1298.726

构件汇总信息明细表(包含措施筋)

工程名称：南苑项目4#楼(导出)

编制日期：2020-09-05

单位：kg

		其他100[10987]	19	39.71		
		其他100[11010]	19	43.32		
		其他120[10968]	19	86.526		
		其他120[10983]	19	112.86		
		其他110[10966]	19	110.58		
		后浇板[10979]	19	7.524		
		合计		1298.726		
柱	1886.32	LTGZ[42857]	76			1886.32
		合计				1886.32